

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Casey of Shamrock Oil & Gas has this date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Shamrock Oil & Gas Corporation

Complete Address: Box 631, Amarillo, Texas

Lease Name: Chara Vail ETAL Well No. 1

Location: 6- SW of NE 4 Sec. 15 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5802.011 Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Casey was instructed to plug the well as follows:

13 3/8" to 640' circulated w/ cement. 9 5/8" to 2675' cemented.

5 1/2" to 4605' cemented. Top perf. 4553'.

Plug bottom w/ 20 sax of cement, top of cement 3872'.

Mud 3872' to 700' Spotted 40 sax cement 700' to 600'

Mud 600' to 45' Plug, Halls & 15 sax of cement 45' to 0'

Very truly yours,

Conservation Division Agent