

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
JAN 18 1966
OFFICE OF THE ATTORNEY GENERAL
STATE OF KANSAS

Operator's Full Name Shamrock Oil & Gas Corp.

Complete Address: Box 631, Amarillo, Texas

Lease Name Chara Vail Etal. Well No. 1

Location C-SW of NE 4 Sec. 15 Twp. 33 Rge. 30 (E) (W)

County Meade Total Depth 5802'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Daco Well Service

Address: Borger, Texas License No. _____

Operation Completed: Hour 5:00 PM Day 16 Month 1 Year 1966

The Above well was plugged as follows:

13 3/8" to 640' circulated w/ cement. 9 5/8" to 2675' Cemented.

5 1/2" to 4605' cemented. Top perf. 4553'.

Plug bottom w/ 20 sax cement; top of cement 3872'

Mud 3872' to 700'. Spotted 40 sax cement 700' to 600'

Mud 600' to 45' Plug, hauls & 15 sax of cement 45' to 0

Pulled 3225' of 5 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. Hugh Cott
Well Plugging Supervisor

DATE 1/18/66

INV. NO. 2620-W