

KANSAS

*af* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 22 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mallonee-Mahomey

Complete Address 925 Sutton Place, Wichita, Kansas

Lease Name Browne Well No. 1

Location C NE SW Sec. 3 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6208'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 9:30 Am Day 20 Month 9 Year 1972

The above well was plugged as follows:

8 5/8" to 1390' circulated w/ cement. 4 1/2" to 5825' cemented.

Top perforations 5583' Plug bottom w/ 20 sacks cement.

Top of cement 5320' Mud 5320' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 2621' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edgar J. Egan*  
Well Plugging Supervisor

INVOICED

DATE 9-22-72

INV. NO. 6354-W