

RP

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mallonee-Mahoney Inc.
Complete Address 925 Sutton Place, Wichita, Kansas
Lease Name Gosgrove Well No. 1
Location SE NW Sec. 4 Twp. 33 Rge. 33 (E) (W)
County Seward Total Depth 6110'
Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling Co.
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 5:00PM Day 5 Month 10 Year 1971

The above well was plugged as follows:

8 5/8" to 1368' circulated w/ cement. 4 1/2" to 5955' cemented.
Top perforations 5646' Plug bottom w/ 20 sacks cement.
Top of cement 5390' Mud 5390' to 900'
Spotted 35 sacks cement 900' to 800' Mud 800' to 45'
Plug, Hull s & 15 sacks cement 45' to 0'. Company Pump
Pulled 2612' of 4 1/2" casing

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Evers
Well Plugging Supervisor

INVOICED

DATE 10-12-71
INV. NO. 4456-W