

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*Authority to Plug issued
Oct 30, 1975*

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Hasada Industries

Complete Address PO Box 782, Liberal, Kansas 67901

Lease Name March Well No. 1

Location C. NE NE Sec. 7 Twp. 33 Rge. (E) (W) 33

County Seward Total Depth 6375

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Liberal, Kans License No. 511

Operation Completed: Hour 2:30 PM Day 8th Month Nov Year 1975

The above well was plugged as follows:

*There was 1595' of 8 1/2" surface casing.
5 1/2" casing set to 6250. Perforations were
from 6079-6084. 1st plug at 6079 with
15 sacks cement and 2 sack cotton seed
hulls. 2nd plug at 1700' with 35 sacks
cement. 3rd plug at 450 with 15 sacks
of cement. There was 2700' of 5 1/2"
casing salvaged.*

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Lawrence Thomas
Well Plugging Supervisor

INVOICED

NOV 10 1975

DATE 11-10-75

CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 2210-W