

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

15-175-20453-0000

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 1517520453-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

8/03

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO

STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE COSGROVE WELL# A-3 SEC. 22 T. 33S R. 34 (xxxx/West)

C - NE - NE SPOT LOCATION/QQQQ COUNTY SEWARD

660 FEET (in exact footage) FROM X/N (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 5-5/8 SET AT 1679 CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 6357 CEMENTED WITH 350 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 6306-6328, 6182-6190, 5900-5910,  
5873-5880. CIBPS: 6250, 6100

ELEVATION 2894 /            T.D. 6360 PBDT 6100 ANHYDRITE DEPTH             
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING DUMP 30 SXS CMT AND 2 SXS HULLS FROM 6100 TO 5745. RU  
JACKS AND SHOOT OFF 4 1/2 CSG AT FREE POINT. TOH AND SPOT 50 SXS CMT FROM 1750 TO 1600.  
TOH AND SPOT 50 SXS CMT FROM 700 TO 550. TOH TO 40 AND SPOT 15 SXS CMT FROM 40 TO 4.  
CUT OFF AND CAP 8 5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEROFD PHONE# (620) 482-1000

ADDRESS 7107 W 2<sup>ND</sup> City/State LIBERAL, KANSAS 67901

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3/28/03 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)  
DIVISION PRODUCTION ENGINEER

RECEIVED

APR 03 2003

KCC WICHITA

1/04



# Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

April 03, 2003

Re: COSGROVE #A-3  
API 15-175-20453-00-00  
CNENE 22-33S-34W, 660 FNL 660 FEL  
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888