

15-175-21100-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92  
**RECEIVED**  
KANSAS CORPORATION COMMISSION

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File **ONE** Copy)

AUG 08 1994

API # 15-175-21,100-0000 (Identifier number of this well). This must be submitted for  
wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE ROWLAND "A" WELL# 1H SEC. 23 T. 33S R. 34 (XXXX West)

SE - SE - NW - NW SPOT LOCATION/QQQQ COUNTY SEWARD

1250 FEET (in exact footage) FROM X (N) (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM X (W) (circle one) LINE OF SECTION (NOT Lease Line)

**Check One:** OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 660' CEMENTED WITH 365 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 2974' CEMENTED WITH 255 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2634-2646, 2664-2704, 2716-2756

ELEVATION 2896.4/-- T.D. 2974 PBDT 2962 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU SARGENTS. SPOT 2 SXS HULLS & 24 SXS CLASS "H" CMT FROM 2634-2500' W/9 PPG MUD. PULL FREE POINT AND CUT OFF 5-1/2" CSG, SPOT 35 SXS CMT @ CUTOFF DEPTH. SPOT 40 SXS CMT @ 650-550'. SPOT 18 SXS CMT @ 53-3'. CUTOFF 8-5/8" CSG 3' BELOW GROUND LEVEL & CAP. RESTORE LOCATION, CLEAN UP.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED?

If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

JERRY RUTTMAN PHONE# (316) 629-4382

ADDRESS P.O. BOX 351 City/State LIBERAL, KANSAS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 8/1/94 AUTHORIZED OPERATOR/AGENT David Keppel for J.L. Ashton  
J.L. ASHTON (signature) DIV. PROD. MGR.

8/94

1/95

11



Kansas Corporation Commission

Joan Finney, Governor    Susan M. Seltsam, Chair    F.S. Jack Alexander, Commissioner    Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director    Brian Moline, General Counsel

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

August 15, 1994

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Rowland "A" #1H  
API 15-175-21,100  
1250 FNL 1250 FWL  
Sec. 23-33S-34W  
Seward County

Dear Jerry Ruttman,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely  
  
David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760