

15-175-20525-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-175-20,525-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549 <sup>8/90</sup>

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Maxwell "B" WELL NO. 1 WELL LOCATION C SW SW COUNTY Seward

SEC. 23 TWP. 33S RGE. 34 ~~X(E)~~ or (W) TOTAL DEPTH 6400 PLUG BACK TD 6363

Check One:

OIL WELL  GAS WELL  D & A  SWD or INJ WELL  DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 1674 CEMENTED WITH 600 Poz/200 Common SACKS

CASING SIZE 4 1/2 SET AT 6399 CEMENTED WITH 120 LW/145 Ss-Poz SACKS

PERFORATED AT 6234-6241 Chester

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING(1). TOH w/rods & tbg. (2). TIH w/CIBP on wireline & set @ 6200'

(dump 2 sxs cmt on top of plug). (3). Load hole w/heavy mud. (4). Find free-point of casing

& shoot off. (5). Spot 50 sxs common cmt @ cut-off. (6). TOH w/casing. (7). Spot 50 sxs

(If additional space is needed use back of form.) (over)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \*No IS ACO-1 FILED? Yes  
(If not explain.) \*Logs are already on file.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon KCC approval.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. A. Ruttman PHONE # (316) 624-6253

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547 <sup>6/90</sup>

ADDRESS Box 506, Liberal, Kansas 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Daniel Kapala for J. L. Ashton  
(Operator or Agent) J. L. Ashton

DATE: 6/6/90 Division Production Mgr.

JUN 11 1990  
CONSERVATION DIVISION  
Wichita, Kansas

①

common cmt @ 1774'. (8). Spot 30 sxs common cmt @ 1000'. (9). Spot 5 sxs common cmt @ 50'.  
(10). Cut-off braden head 3' below GL and weld on cap. (11). Remove surface equipment and  
restore location.

State of Kansas



## Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
 KEITH R. HENLEY CHAIRMAN  
 RICH KOWALEWSKI COMMISSIONER  
 JACK SHRIVER COMMISSIONER  
 JUDITH MCCONNELL EXECUTIVE DIRECTOR  
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
 SHARI FEIST ALBRECHT, DIRECTOR  
 200 Colorado Derby Bldg.  
 202 W. 1st Street  
 Wichita, KS 67202-1286  
 (316) 263-3238

**NOTICE OF RECEIPT OF  
 WELL PLUGGING APPLICATION**

July 17, 1990

Anadarko Petroleum Corporation  
 P.O. Box 351  
 Liberal, KS 67905-0351

Maxwell "B" #1  
 C SW SW 23-33-34W  
 Seward County, KS  
 API No. 15-175-20,525

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. **Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b).** Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

*David P. Williams*

David P. Williams  
 Production Supervisor

District: #1, 304 W. McArtor  
 Dodge City, KS 67801