

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

15-175-20962-0001  
RECEIVED  
JAN 17 2003  
KCC WICHITA

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 1517520962-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549  
(owner/company name) (operator's)  
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO  
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600

LEASE ETZOLD UNIT SOUTH WELL# 6-2 SEC. 27 T. 33S R. 34 (xxxx/West)  
- E/2 - NE - SW SPOT LOCATION/QQQQ COUNTY SEWARD

1980 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)  
2970 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# E-24960

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8 SET AT 1654 CEMENTED WITH 775 SACKS  
PRODUCTION CASING SIZE 5-1/2 SET AT 6460 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 6295-6307

ELEVATION 2923 / XXXX T.D. 6500 PBD 6434 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING TOH WITH TBG AND PKR. DUMP 30 SXS CMT AND 2 SXS HULLS TO PLUG FROM 6434 TO 6180. PULL FREE POINT AND SHOOT OFF 5-1/2 CSG AT +/- 1750. SPOT 60 SXS CMT FROM 1750 TO 1575. TOH TO 600. SPOT 40 SXS CMT FROM 600 TO 480. TOH TO 40. SPOT 15 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8-5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES  
If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEFORD PHONE# (620) 482-1000  
ADDRESS 1707 W. 2ND City/State LIBERAL, KS 67901

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151  
(company name) (contractor's)  
ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/13/2003 AUTHORIZED OPERATOR/AGENT: Craig R. Walters  
CRAIG R. WALTERS, P.E. (Signature)  
DIVISION PRODUCTION ENGINEER



## *Kansas Corporation Commission*

*Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### **NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Anadarko Petroleum Corporation  
1201 Lake Robbins Drive  
The Woodlands, TX 77380

January 22, 2003

Re: ETZOLD UNIT SOUTH #6-2  
API 15-175-20962-00-00  
E2NESW 27-33S-34W, 1980 FSL 2310 FEL  
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely

A handwritten signature in black ink that reads "David P. Williams".

David P. Williams  
Production Supervisor