

RECEIVED

FEB 24 2003

KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

15475-20375-0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 1517520375-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

8/03

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)
ADDRESS 701 S. TAYLOR, STE 400 CITY AMARILLO
STATE TEXAS ZIP CODE 79101 CONTACT PHONE (806) 457-4600
LEASE FINCHAM WELL# A-4 SEC. 29 T. 33S R. 34 (xxxx/West)
- C - SE - NE SPOT LOCATION/QQQQ COUNTY SEWARD

1980 FEET (in exact footage) FROM X/N (circle one) LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8 SET AT 1689 CEMENTED WITH CIRCULATED SACKS
PRODUCTION CASING SIZE 5 1/2 SET AT 6328 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: PERFS: 6235-6254

ELEVATION 2926 / XXX T.D. 6350 PBSD 6286 ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING DUMP 2 SXS HULLS AND 20 SXS CMT TO PLUG FROM 6286 TO 6130. LOAD HOLE WITH 9 PPG MUD. SHOOT OFF 5 1/2 CSG @ +/- 1740. SPOT 50 SXS CMT FROM 1740 TO 1590. TOH TO 700. SPOT 50 SXS FROM 700 TO 550. TOH TO 40. SPOT 15 SXS CMT FROM 40 TO 4. CUT OFF AND CAP 8 5/8 CSG 4 BELOW GL.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? YES

If not explain why? LOGS SUBMITTED W/ ORIG. COMPLETION REPORT OR DRILLER'S LOG.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID RELEFORD PHONE# (620) 482-1000

ADDRESS 1707 W 2ND City/State LIBERAL, KS

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/17/03 AUTHORIZED OPERATOR/AGENT: Craig R. Walters

CRAIG R. WALTERS, P.E. (Signature)
DIVISION PRODUCTION ENGINEER

1/04



Kansas Corporation Commission

Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

February 26, 2003

Re: FINCHAM A #4
API 15-175-20375-00-00
CSENE 29-33S-34W, 1980 FNL 660 FEL
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888