

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23456-00-00  
Spot: E2SWSW Sec/Twnshp/Rge: 6-7S-22W  
660 feet from S Section Line, 990 feet from W Section Line  
Lease Name: FOUNTAIN TRUST Well #: 6-1  
County: GRAHAM Total Vertical Depth: 3880 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3877		615 SX
SURF	8.625	321		195 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2015 8:30 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: BOB PLANTE Company: QUALITY OIL WELL CEMENTING Phone: (785) 434-7434

Proposed Plugging Method: Ordered 310 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel.  
Port Collar at 2013' w/410 sx cement.  
Perforations: 3624' - 3630', 3676' - 3682', 3750' - 3754', 3770' - 3773', 3780' - 3783'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2015 9:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/200 # hulls followed by 12 sx gel, followed by 225 sx cement w/300 # hulls. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 200 psi.

GPS: 39.46824 -099.82289


Perfs:

Top	Bot	Thru	Comments
3781			
3780	3783		
3773			
3770	3773		
3752			
3750	3754		
3676	3682		

Remarks: QUALITY CEMENT TICKET # 1118

Plugged through: CSG

District: 04

Signed  (TECHNICIAN) CM

JAN 20 2015

Received  
KANSAS CORPORATION COMMISSION

CKM 2/4/15

JAN 30 2015

CONSERVATION DIVISION  
WICHITA, KS