

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-25896-00-00
Spot: NESWNWNE **Sec/Twnshp/Rge:** 33-23S-16E
4463 feet from S Section Line, 2192 feet from E Section Line
Lease Name: FULLER **Well #:** 22
County: WOODSON **Total Vertical Depth:** 1120 feet

Operator License No.: 35122
Op Name: LAKESHORE OPERATING, LLC
Address: 13505 S. MUR-LEN RD SUITE 105-182
OLATHE, KS 66062

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1100		138 SX
SURF	7	40		12 SX

Well Type: OIL **UIC Docket No:** **Date/Time to Plug:** 12/15/2014 12:00 AM
Plug Co. License No.: 5491 **Plug Co. Name:** W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: GREG JACKMAN **Company:** **Phone:** (620) 363-4887

Proposed Plugging Method: Spot a balanced cement plug across perforation via 1" run to 20' off bottom. Spot additional plugs while pulling 1" out of the hole so as to cement wellbore from perforations to surface.

Plugging Proposal Received By: **WitnessType:** NONE
Date/Time Plugging Completed: 12/15/2014 8:00 AM **KCC Agent:** RYAN DULING

Actual Plugging Report:
Ran 1" pipe down the 4.5" casing to TD. Pumped and circulated cement through the 1" pipe inside the 4.5" casing from TD to surface. Pulled the 1" pipe from the well and hooked onto the 4.5" casing and squeezed well. Shut well in under pressure.

Perfs:

Top	Bot	Thru	Comments
1084	1094		

**RECEIVED
KCC DIST # 3
JAN 27 2015
CHANUTE, KS**

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
JAN 29 2015
CONSERVATION DIVISION
WICHITA, KS

2/4/15 ckm Form CP-2/3