

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-21650-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 12-14S-16W  
4682 feet from S Section Line, 3021 feet from E Section Line  
Lease Name: SCHULTE B Well #: 1  
County: ELLIS Total Vertical Depth: 3432 feet

Operator License No.: 31385  
Op Name: M G OIL INC  
Address: PO BOX 162  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3422		125 SX
SURF	8.625	226		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2015 9:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: CURTIS COUNTS Company: M G OIL INC. Phone: (785) 483-1627

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2015 9:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 1450', 990' and 200'.  
Ran tubing to 3175' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 2000' and pumped 75 sx cement. Pulled tubing to 635' and pumped 55 sx cement. Cement circulated. POOH. Hooked to casing and pumped 25 sx cement at 300 psi. Shut in. Braden head was dug out but unable to pump cement into it.

GPS: 38.77545 -098.37590

Perfs:

Top	Bot	Thru	Comments
3193	3195		
3183			
3172	3176		
3144	3147		
3117	3119		

Remarks: QUALITY CEMENTING TICKET # 998

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

2/4/15 CKM

JAN 22 2015

JAN 30 2015

CONSERVATION DIVISION  
WICHITA, KS