

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-28870-00-00
Spot: SENEENENW Sec/Twnshp/Rge: 16-24S-17E
360 feet from N Section Line, 2500 feet from W Section Line
Lease Name: LITTLE KRAMER Well #: 4-14
County: WOODSON Total Vertical Depth: 1242 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN RD
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	7	34		12 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/30/2014 12:00 AM
Plug Co. License No.: 34036 Plug Co. Name: LEIS OIL SERVICES, LLC
Proposal Rcvd. from: GREG LAIR Company: _____ Phone: (620) 468-2681

Proposed Plugging Method: 50 ft plug at 1242' w/10 sks, 50 ft plug at 450' w/10 sks, plug 250' to surface w/55 sks cement.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 09/30/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran drill stem to TD. Hooked onto drill stem and broke circulation. Gelled hole. Pumped and placed 10 sacks of cement at TD. Pulled drill stem up to 450'. Pumped and placed 10 sacks of cement at 450'. Pulled drill stem up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the drill stem and topped the well off with cement. A total of 75 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JAN 27 2015
CHANUTE, KS

RD

Remarks:

Plugged through: DP

District: 03

Signed _____

(TECHNICIAN)

2/4/15 CKM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 29 2015

CONSERVATION DIVISION
WICHITA, KS