

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21801-00-00  
Spot: NWSE Sec/Twnshp/Rge: 10-35S-5W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: WILLIAMS Well #: 10-1  
County: HARPER Total Vertical Depth: 5300 feet

Operator License No.: 31253  
Op Name: PRIMEXX OPERATING CORPORATION  
Address: 4849 GREENVILLE # 1600  
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		4960		
PROD	5.5	2599		225 SX
PROD	5.5	5299	2500	225 SX
SURF	8.625	421		350 SX
T1	2.875	5129		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/01/2014 12:00 AM  
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.  
Proposal Rcvd. from: MATT Company: JERRY DUNKIN Phone: (580) 237-6152

Proposed Plugging Method: CIBP 5000' & 2 SXS. 35 SXS @ 1000'. 35 SXS @700'. CIRCUALTE 470' TO 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/20/2015 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP @ 5000' & 3 SXS. PULLED 2500' OF 5 1/2". RAN TUBING TO 1000'  
SPOTTED 35 SXS CEMENT. PULLED TUBING TO 700' SPOTTED 35 SXS CEMENT  
TAG @ 650'. PULL TUBING TO 470' & CIRCUALTE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5060	5080	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION  
**FEB 02 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: JERRY DUNKIN CEMENT. COMMON 3% CACL.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

CKM 2/4/15