

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21804-00-00
Spot: W2E2SEW Sec/Twnshp/Rge: 10-35S-5W
1980 feet from N Section Line, 2080 feet from W Section Line
Lease Name: WILLIAMS Well #: 10-2
County: HARPER Total Vertical Depth: 5300 feet

Operator License No.: 31253
Op Name: PRIMEXX OPERATING CORPORATION
Address: 4849 GREENVILLE # 1600
DALLAS, TX 75206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	5300	3215	225 SX
SURF	8.625	421		350 SX
T1	2.875	4956		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2014 12:00 AM
Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.
Proposal Rcvd. from: MARTY WADE/ JERY OGLE Company: JERRY DUNKIN, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 5000' & 2 SXS. RECOVERED 68 JOINTS @ 3215'. 1000' 35 SXS, 700' 35 SXS. 470'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2015 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET @ 5000' TO COVER PERFS. THE BP WAS CAPPED WITH 3 SXS CEMENT. THE CASING WAS RECOVERED FROM 3215' AND PULLED FROM WELL BORE. TUBING WAS RUN TO 1000' AND SPOTTED 35 SXS CEMENT. PULLED TO 700' SPOTTED 35 SXS CEMENT. PULLED TO 470' & CIRCUALTE CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5080	5092		


RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: JERRY DUNKIN CEMENT. COMMON 3% CACAL

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

CCM 2/4/15