

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-22272-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 8-14S-21W  
2310 feet from S Section Line, 1220 feet from W Section Line  
Lease Name: NORBERT Well #: 1  
County: TREGO Total Vertical Depth: 4103 feet

Operator License No.: 5252  
Op Name: R. P. NIXON OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4081		125 SX
SURF	8.625	219		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/15/2015 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DUANE ACHTERBERG Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 656-0038

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls and 14 sx gel.  
DV Tool at 1629' w/350 sx cement.  
Perforations at 3980' - 3984'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/15/2015 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3900' and pumped 14 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1750' and pumped 200 sx cement with good circulation of cement. Pulled tubing. Topped off casing w/25 sx cement full. Tied on to backside and squeezed w/5 sx cement. Shut in pressure 300 psi.

GPS: 38.84813 -099.68431

Perfs:

Top	Bot	Thru	Comments
3980	3984		

Remarks: ALLIED CEMENTING TICKET # 055620

Plugged through: TBG

District: 04

Signed

  
\_\_\_\_\_  
(TECHNICIAN)  
KANSAS CORPORATION COMMISSION

CM 2/4/15

CM

JAN 20 2015

JAN 30 2015

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS