

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25396-01-00  
Spot: S2S2SESE Sec/Twnshp/Rge: 3-18S-21W  
187 feet from S Section Line, 627 feet from E Section Line  
Lease Name: PABST FARM 3H Well #: 2  
County: NESS Total Vertical Depth: 4691 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	4400		WITH 60 SX CMT
COND	14	60		WITH 56 SX CMT
II	7	4691	1399	WITH 280 SX CMT
PROD	4.5	8715	0	WITH 315 SX CMT
SURF	9.625	1366		WITH 590 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/16/2015 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 798-2300

Proposed Plugging Method: CIBP @ 4400' WITH 60 SX CMT. PLUG AT 1450' WITH 80 SX CMT. PLUG AT 870' WITH 80 SX CMT. PLUG AT 350' WITH 60 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/16/2015 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4400' WITH 60 SX CMT. SHOT OFF CASING AT 1664'. 1ST PLUG AT 1460' WITH 80 SX CMT. 7" CASING STUCK IN HOLE. SHOT CASING OFF AT 1195'. 2ND PLUG AT 907' WITH 80 SX CMT. 3RD PLUG AT 354' WITH 60 SX CMT. 4TH PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8420	8619		
7892	8223		
7496	7827		
7100	7432		
6704	7036		
6309	6639		
5912	6243		
5516	5848		
5120	5452		
4724	5056		

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 02 2015

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES. TMD=8725'.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

CKM 2/4/15

ST