

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25431-01-00
Spot: NWNENWNW Sec/Twnshp/Rge: 11-18S-21W
252 feet from N Section Line, 699 feet from W Section Line
Lease Name: J & A ASSOCIATES 11H Well #: 1
County: NESS Total Vertical Depth: 4696 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4375		WITH 60 SX CMT
COND 14		71		WITH 60 SX CMT
L1 4.5		8562		WITH 470 SX CMT
PROD 7		4696	1686	WITH 270 SX CMT
SURF 9.625		1365		WITH 590 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/12/2015 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: SET CIBP @ 4375' WITH 60 SX CMT. PLUG AT 1450' WITH 80 SX CMT. PLUG AT 870' WITH 80 SX CMT. PLUG AT 350' WITH 60 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2015 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4375' WITH 60 SX CMT. 1ST PLUG AT 1460' WITH 80 SX CMT. 2ND PLUG AT 830' WITH 80 SX CMT. 3RD PLUG AT 328' WITH 60 SX CMT. 4TH PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
8157	8466		
7776	8095		
7395	7714		
7014	7333		
6633	6952		
6252	6571		
5871	6190		
5490	5809		
5109	5428		
4728	5047		

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2015

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES. TMD=8565'.

Plugged through: CSG

District: 01

RECEIVED
JAN 21 2015
KCC DODGE CITY

Signed Michael J Maier
(TECHNICIAN)
CRM 2/4/15

SP