

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02794-00-00  
Spot: NENESW Sec/Twnshp/Rge: 32-13S-17W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: HOFFMAN LEASE Well #: 1  
County: ELLIS Total Vertical Depth: 3601 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| L1     | 4.5   | 1500       |             | 75 sx    |
| PROD   | 5.5   | 3576       |             | 50 SX    |
| SURF   | 8.625 | 280        |             | 180 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2015 9:00 AM  
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC  
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Perforations: 3318 - 3595 OH

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2015 1:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 1950' and 1260'. Berexco ran in hole with tubing to 3494'. Quality rigged to tubing and mixed and pumped 75 sx cement w/300 # hulls mixed in. Pulled tubing to 2848' and pumped 130 sx cement w/200 # hulls mixed in. Pulled tubing to 1514' and pumped 100 sx cement to circulate cement up 5 1/2" casing. Pulled tubing and topped off 5 1/2" casing w/25 sx cement. Hole standing full. 4 1/2" liner to 5 1/2" casing full of cement. Rigged to 8 5/8" surface casing and pumped 5 sx cement to pressure w/200 psi. Shut in pressure 200 psi.

GPS: 38.87739 -099.23597

Remarks: QUALITY OILWELL CEMENTING TICKET # 1117

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Received (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

CA

JAN 15 2015

JAN 30 2015

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS

CKM 2/4/15