

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21637-00-01
Spot: NWNESE Sec/Twnshp/Rge: 22-9S-19W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: PEKAREK SE Well #: 1
County: ROOKS Total Vertical Depth: 3624 feet

Operator License No.: 33263
Op Name: BOWMAN, WILLIAM F. DBA THE BILL
Address: 2640 W RD
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3697		125 SX
SURF	8.625	215		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2015 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BILL BOWMAN Company: BILL BOWMAN OIL CO. Phone: (785) 259-1297

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 100 # hulls and 15 sx gel spacer. OWWO well, 1st plugged on 12/09/1985.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2015 11:40 AM KCC Agent: PAT BEDORE

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 3533' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1600' and pumped 100 sx cement. Pulled tubing to 800' and pumped 100 sx cement to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing w/15 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pressured to 350 psi immediatley.
GPS: 39.25536N -099.42254W

Remarks: ALLIED CEMENTING TICKET # 055623

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

CKM 2/4/15

Form CP-2/3

JAN 28 2015

JAN 30 2015

CONSERVATION DIVISION
WICHITA, KS