

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-21890-00-00  
Spot: W2W2NW Sec/Twnshp/Rge: 26-14S-15W  
3967 feet from S Section Line, 4993 feet from E Section Line  
Lease Name: WAUDBY Well #: 3  
County: RUSSELL Total Vertical Depth: 3303 feet

Operator License No.: 32286  
Op Name: BROWN, RODNEY DBA MJT OIL  
Address: 115 3RD ST BOX 112  
GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3302		100 SX
SURF	8.625	242		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2015 9:30 AM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: AVEN WEAVERLING Company: M J T OIL Phone: (785) 623-3221

Proposed  
Plugging  
Method:

Ordered 350 sx 60/40 pozmix 4% gel cement, 10 sx gel and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforations: 1400', 945' and 210'.  
Ran tubing to 3185' and pumped 10 sx gel and 75 sx cement w/100 # hulls. Pulled tubing to 1425' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 425' and pumped 50 sx cement. Circulated cement to pit. POOH and topped off w/10 sx cement. Hooked to braden head and pumped 25 sx cement. Cement started to come around in 5 1/2" casing. Shut in w/200 psi.

GPS: 38.80918 -098.96495

Remarks: QUALITY CEMENTING TICKET # 1088

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

2/4/15 CKM

Form CP-2/3

JAN 22 2015

JAN 30 2015

CONSERVATION DIVISION  
WICHITA, KS