

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22167-00-00
Spot: NWSENE Sec/Twnshp/Rge: 7-27S-12W
1905 feet from N Section Line, 922 feet from E Section Line
Lease Name: POLLOCK Well #: 3
County: PRATT Total Vertical Depth: 4336 feet

Operator License No.: 31056
Op Name: BULLSEYE OILFIELD SERVICE
Address: 10308 NE 30TH AVE PO BOX 8778
PRATT, KS 67124

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 4345 | 1680 | WITH 153 SX CMT |
| SURF | 8.625 | 366 | | WITH 225 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/12/2015 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 4125' & 5 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/13/2015 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4100' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 729' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 422' WITH 50 SX CMT. LOST RETURNS WHILE SPOTTING PLUG. SHUT DOWN & LET CMT SET. 1/13/15: TAG TOC @ 545'. PULLED TBG TO 400'. SPOTTED 50 SX CMT AT 400'. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4176 | 4180 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Steve Pfeifer
(TECHNICIAN)
CKM 2/1/15

RECEIVED
JAN 21 2015
KCC DODGE CITY