

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22169-00-01
Spot: E2NE Sec/Twnshp/Rge: 7-27S-12W
3847 feet from S Section Line, 573 feet from E Section Line
Lease Name: POLLOCK Well #: 5
County: PRATT Total Vertical Depth: 2887 feet

Operator License No.: 31056
Op Name: BULLSEYE OILFIELD SERVICE
Address: 10308 NE 30TH AVE PO BOX 8778
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2780		
PROD	5.5	2887	2180	WITH 124 SX CMT
SURF	8.625	312		WITH 275 SX CMT

Well Type: SWD UIC Docket No: D28019.0 Date/Time to Plug: 01/08/2015 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SET CIBP @ 2480' WITH 2 SX CMT OR SAND TO 2480' WITH 5 SX CMT. PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/12/2015 10:30 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SAND BACK TO 2470' & 5 SX CMT. 1ST PLUG AT 722' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. DID NOT CIRCULATE. TAGGED TOC @ 189'. TOPPED OFF WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2792	2796		
2552	2562		
2532	2542		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Robert Dickerson
(TECHNICIAN)

CC:UIC
CKM 2/4/15

RECEIVED
JAN 24 2015
KCC DODGE CITY