

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-22529-00-00
Spot: SENESWNW Sec/Twnshp/Rge: 22-16S-28W
1670 feet from N Section Line, 1250 feet from W Section Line
Lease Name: SHAY Well #: 1
County: LANE Total Vertical Depth: 4579 feet

Operator License No.: 35066
Op Name: CATO EXPLORATION, LLC
Address: 15 EAST 5TH ST., STE 2100
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3980		WITH 2 SX CMT
CIBP		4080		WITH 1 SX CMT
PROD	5.5	4360	2111	WITH 190 SX CMT
SURF	8.625	1432		WITH 650 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/22/2015 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 3980' WITH 2 SX CMT. PLUG AT 2100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 1480' WITH 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLGU AT 240' TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 01/22/2015 12:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

CIBP @ 3980' WITH 2 SX CMT. 1ST PLUG AT 2117' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 1491' WITH 50 SX CMT. 3RD PLUG AT 713' WITH 50 SX CMT. 4TH PLUG AT 259' WITH 80 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
4167	4170		
4134	4142		
4012	4019		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY PHIL DOLLAR.

Plugged through: TBG

District: 01

Signed Larry J Harris PIRT JT
(TECHNICIAN)

CKM 2/4/15

RECEIVED
JAN 24 2015
KCC DODGE CITY

[Handwritten Signature]