

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20590-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 10-31S-17W
990 feet from S Section Line, 354 feet from W Section Line
Lease Name: UNRUH Well #: 1
County: COMANCHE Total Vertical Depth: 5198 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4992		WITH 2 SX CMT
PROD	4.5	5197	1925	WITH 100 SX CMT
SURF	8.625	611		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/16/2015 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4990' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/16/2015 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4992' WITH 2 SX CMT. 1ST PLUG AT 1036' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 656' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 20 SX CMT. CMT CIRCULATED. 1/21/15: CEMENT FELL 400'. TOPPED OFF WITH 110 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5042	5060		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

CKM 2/4/15

RECEIVED
JAN 21 2015
KCC DODGE CITY