

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-20794-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 22-31S-17W  
763 feet from S Section Line, 1938 feet from E Section Line  
Lease Name: PEPPERD A Well #: 2-22  
County: COMANCHE Total Vertical Depth: 5040 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4880		WITH 2 SX CMT
PROD	4.5	5037	2043	WITH 165 SX CMT
SURF	8.625	602		WITH 450 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/21/2015 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4880' WITH 2 SX CMT. PLUG AT 1020' WITH 15 SX GEL & 50 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/21/2015 11:20 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4880' WITH 2 SX CMT. 1ST PLUG AT 1023' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 652' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 70 SX CMT, CIRCULATING 40 SX CMT TO PIT.

Perfs:

Top	Bot	Thru	Comments
4948	4957		
4937	4942		

RECEIVED  
KANSAS CORPORATION COMMISSION  
FEB 02 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

CKM 2/4/15

RECEIVED  
JAN 24 2015  
KCC DODGE CITY

Form CP-2/3