

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-067-21086-00-01
Spot: SWSW Sec/Twnshp/Rge: 11-30S-35W
659 feet from S Section Line, 4529 feet from E Section Line
Lease Name: MLP STUBBS Well #: B-1 SWD
County: GRANT Total Vertical Depth: 5850 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1340		
DVT		3116		WITH 450 SX CMT TO 0'
PLG	5.5	2468		
PROD	5.5	5849	0	WITH 610 SX CMT
SURF	8.625	1793		WITH 375 SX CMT

Well Type: SWD UIC Docket No: D27685.0 Date/Time to Plug: 01/26/2015 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: TAG TD WITH DEPTHOMETER IF ABLE. RTIH TO 1750'. SPOT 25 SX CMT. SET CIBP @ 1340'. CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/26/2015 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

TAGGED SAND FILL-UP AT 1900' WITH DEPTHOMETER. RAN TBG IN HOLE TO 1720' & SPOTTED 25 SX CMT. PULLED TBG OUT OF HOLE & SET CIBP @ 1340'. RAN TBG IN HOLE AT 1340' CIRCULATED TO SURFACE WITH 140 SX CMT. PULLED TBG OUT OF HOLE. TOPPED OFF WITH 16 SX CMT. HOOKED UP TO BACKSIDE & PUMPED 20 SX CMT TO 710 PSI. PRESSURE HELD.

Perfs:

Top	Bot	Thru	Comments
1390	1410		

RECEIVED
KANSAS CORPORATION COMMISSION

FEB 02 2015

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JAN 29 2015
KCC DODGE CITY

Signed Larry Harris
(TECHNICIAN)

cc:uic
CKM 2/4/15