

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-31168-00-00
Spot: NWSWNESW Sec/Twnshp/Rge: 4-24S-18E
1795 feet from S Section Line, 1485 feet from W Section Line
Lease Name: BAKER Well #: BJ-4
County: ALLEN Total Vertical Depth: 1161 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	32		10 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/21/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 11/21/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran drill stem to TD. Hooked onto drill stem and broke circulation. Gelled hole. Pumped and placed 50 sacks of cement at TD. Pulled drill stem up to 500'. Pumped and placed 15 sacks of cement at 500'. Pulled drill stem up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the drill stem and topped the well off with cement. A total of 120 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JAN 27 2015
CHANUTE, KS

RD

Remarks:

Plugged through: DP

District: 03

Signed [Signature]
(TECHNICIAN)
CKM 2/4/15

Received
KANSAS CORPORATION COMMISSION

JAN 29 2015

CONSERVATION DIVISION
WICHITA, KS