

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-31172-00-00  
Spot: NWSESWNW Sec/Twnshp/Rge: 4-24S-18E  
3135 feet from S Section Line, 890 feet from W Section Line  
Lease Name: MURPHEY Well #: MD4  
County: ALLEN Total Vertical Depth: 1250 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	32		10 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2014 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed  
Plugging  
Method:

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 12/03/2014 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Perfs:

Ran drill stem to TD. Hooked onto drill stem and broke circulation. Gelled hole. Pumped and placed 60 sacks of cement at TD. Pulled drill stem up to 500'. Pumped and placed 15 sacks of cement at 500'. Pulled drill stem up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the drill stem and topped the well off with cement. A total of 160 sacks of portland cement was reported used to plug this well.

RECEIVED  
KCC DIST # 3  
JAN 27 2015  
CHANUTE, KS

RD

Remarks:

Plugged through: DP

District: 03

Signed \_\_\_\_\_

*[Signature]*  
(TECHNICIAN)  
CKM 2/4/15

Received  
KANSAS CORPORATION COMMISSION

JAN 29 2015

CONSERVATION DIVISION  
WICHITA, KS