

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-02602-00-00
Spot: SENE SW Sec/Twnshp/Rge: 8-14S-14W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KRUG Well #: 3
County: RUSSELL Total Vertical Depth: 3085 feet

Operator License No.: 33959
Op Name: GINTHER OIL, INC.
Address: 524 NORTH ST. JOHN STREET
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	10	892	892	
PROD	7	3051		
SURF	8.625	2300		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/25/2012 8:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: MILTON Company: GINTHER OIL OPERATIONS Phone: (785) 483-6575

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 600 # hulls and 13 sx gel.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/25/2012 8:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report: _____ Perfs: _____

Perforations: 1450', 880' and 500'.
Ran tubing to 2700' and pumped 13 sx gel followed by 150 sx cement w/400 # hulls. Pulled tubing to 890' and pumped 130 sx cement w/200 # hulls. Cement circulated in cellar. POOH and filled casing w/20 sx cement. Hole stayed full.
GPS: 38.84656 -098.90237

Remarks: QUALITY CEMENTING TICKET # 6010

Plugged through: TBG

District: 04

Signed Ray A Dinkel
Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION CM

JAN 22 2015

JAN 30 2015 CKM 2/4/15
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3