

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-12691-00-01
Spot: E2W2SW Sec/Twnshp/Rge: 36-21S-12W
1305 feet from S Section Line, 958 feet from W Section Line
Lease Name: SITTNER Well #: 4
County: STAFFORD Total Vertical Depth: 3612 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3470		WITH 2 SX CMT
PROD	5.5	3570	873	WITH 125 SX CMT
SURF	8.625	243		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/08/2015 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 3470' WITH 2 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2015 11:20 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3470' WITH 2 SX CMT. 1ST PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3567	3612		
3520	3525		

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 02 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
JAN 24 2015
KCC DODGE CITY [Signature]

CKM 2/4/15

[Signature]