

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 20 1967
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ninny of Cities Service Oil has this
date requested permission to plug the following described well:

Mr. Ninny guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 6, Liberal, Kansas

Lease Name: Salley "F" Well No. 1

Location: SE NW SW Sec. 28 Twp. 33 Rge. 32 (E) (W)

County Seward Total Depth 6120' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ninny was instructed to plug the well as follows:

8 5/8" to 1432' circulated w/ cement. 5 1/2" to 6120' cemented

Top perforations 5662' Plug bottom w/ 75 sacks cement

top of cement 5200' Mud 5200' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, HULLS & 15 sacks cement 45' to 0'

Very truly yours,

Edgard J. Eves
Conservation Division Agent