

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1974

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

NOV 4 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Burriss of Rains & Williams has this date requested permission to plug the following described well:

Mr. Burriss guarantees payment of the plugging fee.

Operator's full Name: Hoover & Bracken

Complete Address: 3232 Liberty Towers, Okla city, Okla 73102

Lease Name: Davis Well No. 1-36

Location: ~~Platte~~ C. N. 1/2 Sec. 36 Twp. 33 Rge. (E)(W) 32

County: \_\_\_\_\_ Total Depth 5723 Oil Well \_\_\_\_\_

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A  Lost Hole \_\_\_\_\_

Mr. Burriss was instructed to plug the well as follows:

8 5/8" surface pipe set 1393 ft. Fill hole with heavy mud from 5723 to 900 ft. 50 sacks cement then fill hole with heavy mud to 400 ft 35 sacks cement. Fill hole with heavy mud to 45 ft 15 sacks of cement. Plugging was done by Halliburton Cementing of Liberal, Mo through 4 1/2" drill pipe

Very truly yours,

Charles J. Thomas  
Conservation Division Agent