

15-175-10010-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hanna of Anadarko Prod. Co. has this
date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Keller "B" Well No. 1

Location: App G E/2 NE SW Sec. 24 Twp. 33 Rge. 32 (E) (W)

County: Seward Total Depth 6033' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1440' circulated w/ cement. 4 1/2" to 6032' cement.


Top perforations 5676' Plug bottom w/ 15 sacks cement

Top of cement 5410' Mud 5410' to 900'

Spot 40 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 00'.

Very truly yours,


Conservation Division Agent