

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 22 1972

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Mallonee-Mahoney has this
date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney

Complete Address: 925 Sutton Place, Wichita, Kansas

Lease Name: Browne Well No. 1

Location: G NE SW Sec. 3 Twp. 33 Rge. 33 (E) (W)

County: Seward Total Depth 6208' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 1390' circulated w/ cement. 4 1/2" to 5825' cemented.


Top perforations 5583' Plug bottom w/ 20 sacks cement.

Top of cement 5320' Mud 5320' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent