

15-175-20179-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Mallonee has this

date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney Inc.

Complete Address: Box 1257, Liberal, Kansas

Lease Name: Cosgrove "A" Well No. 1

Location: NW/4 Sec. 4 Twp. 33 Rge. 33 (E)(W)

County: Seward Total Depth 5800' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 422' circulated w/ cement. 4 1/2" to 5799' cemented.

Top perforations 5596' Plug bottom w/ 20 sacks cement.

Top of cement 5494' Mud 5494' to 900'

Spot 25 sacks cement 900' to 800' Mud 800' to 45'

Plug, Halls ~ 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Coes
Conservation Division Agent