

R

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clift of Mallonee-Mahoney has this

date requested permission to plug the following described well:

Mr. Clift guarantees payment of the plugging fee.

Operator's full Name: Mallonee-Mahoney

Complete Address: 925 Sutton Place, Wichita, Kansas

Lease Name: Cosgrove Well No. 1

Location: SE NW Sec. 4 Twp. 33 Rge. 33 <sup>XX</sup>(E)(W)

County: Seward Total Depth 6110' Oil Well     

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Clift was instructed to plug the well as follows:

8 5/8" to 1368' circulated w/ cement . 4 1/2" to 5955' cemented.

Top perforations 5646' Plug bottom w/ 20 sacks cement.

Top of cement 5390' Mud 5390' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, HULLS & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent