



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Gattin of Anadarko Production Co. has this date requested permission to plug the following described well:

Mr. Gattin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name: Browne A Well No. # 1

Location: C NW SE Sec. 9 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6400' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gattin was instructed to plug the well as follows:

8 5/8"-1600' Circulated w/cement. 4 1/2"-6120' Cemented. Plug back-6081'

Top perforations-6004'. Plug bottom w/20 Sax.cement top cement-5800'

Mud 5800' to 700' Spotted 35 Sax.cement 700' to 600'

Mud 600' to 45' Plug, 15 Sax.cement 45' to 0

Very truly yours,

[Handwritten Signature]
Conservation Division Agent