

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sargent of Anadarko Production Co. has this  
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name: Sante Fe Land Improvement Co. Well No. 2-A

Location: App. C SE NE Sec. 9 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 6125' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Sargent was instructed to plug the well as follows:

8 5/8 to 1568' Circulated W/ cement. 4 1/2" to 6124' cemented.

Top perforations 6024'. Plug bottom W/ 20 sax cement,

Top cement 5800'. Mud 5800' to 700'.

Spotted 35 sax of cement 700' to 600'. Mud 6000 to 45'

Plug, Hulls & 15 sax cement 45' to 0.

Very truly yours,

*Hugh Roberts*  
Conservation Division Agent