

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAP 23 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Troy of Cities Service has this
date requested permission to plug the following described well:

Mr. Troy guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil

Complete Address: Box 1098, Liberal, Kansas

Lease Name: Hunt "B" Well No. 1

Location: App Center Sec. 14 Twp. 33 Rge. 33 (E) (W)

County: Seward Total Depth 2745' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Troy was instructed to plug the well as follows:

8 5/8" to 880' circulated w/ cement. 5 1/2" to 2745' circulated w/ cement.

Top perforations 2574' Plug bottom w/ 20 sacks cement.

Top of cement 2534' Mud 2534' to 958'

Spot 15 sacks cement 958' to 853' Mud 853' to 50'

Plug, Halls & 5 sacks cement 50' to 0'.

Very truly yours,

[Signature]
Conservation Division Agent