

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Investors has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Investors Drilling & Exploration

Complete Address: Box 617, Liberal, Kansas

Lease Name: Headrick Well No. 1

Location: C SW NW Sec. 1 Twp. 33 Rge. 31 XX (E) (W)

County: Seward Total Depth 6065' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

8 5/8" to 1520' circulated w/ cement. Mud 6065' to 1000'

Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, H^ulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward E. Lewis
Conservation Division Agent