

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Dunkin of Cleary Petroleum has this

date requested permission to plug the following described well:

Mr. Dunkin guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum Inc.

Complete Address: 310 Kermac Building, Oklahoma City, Okla.

Lease Name: Sheldon Well No. 1

Location: SW SW Sec. 14 Twp. 33 Rge. 31 KE (W)

T.D. 6063'

County Seward Total Dept 5650' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Dunkin was instructed to plug the well as follows:

8 5/8" to 150' circulated w/ cement. 5 1/2" to 6063' cemented

Top perforations 4910' Plug bottom w/ 25 sacks cement

Top of cement 4878' Mud 4878' to 900'

Spot 35 sacks cement 900' to 800' Mud 800' to 180'

Spot 30 sacks cement 180' to 80' Mud 80' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edgar J. Evers  
Conservation Division Agent