



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duncan of White Shield has this date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.

Operator's full Name: White Shield Oil & Gas Corporation

Complete Address: Box 2139 Tulsa, Oklahoma

Lease Name: Headrick "A" Well No. 2-1

Location: C SW SE Sec. 2 Twp. 33 Rge. 31 (E) (W)

County: Seward Total Depth 6045' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole SWD Well

Mr. Duncan was instructed to plug the well as follows:

8 5/8" to 1609' circulated w/ cement. 5 1/2" to 6039' cemented.

Top perforations 3073' Plug bottom w/ 20 sacks cement

Top of cement 2800' Mud 2800' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent