

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Sante Fe Land Improvement Co. Well No. 2"A"

Location APP. C SE NE Sec. 9 Twp. 33 Rge. 33 (W)

County Seward Total Depth 6125'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargent Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 8:00PM Day 18 Month 1 Year 1966

The Above well was plugged as follows:

8 5/8"-1568' Circulated with cement. 4 1/2"-6124' Cemented.

Top perforations 6024'- Plug Bottom W/ 20 sax Of cement,

Top of cement 5800'. Mud 5800' to 700'.

Spotted 35 sax cement 700' to 600'. Mud 600' to 45'.

Plug, Halls & 15 sax cement 45' to 0.

Pulled 2308' of 4 1/2" casing. Company Pump

I hereby certify that the above well was plugged as herein stated.

Signed: 
Well Plugging Supervisor

1/20/66
2629-W