

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Cities Service Oil Co.

Complete Address Box 1098, Liberal, Kansas 67901

Lease Name Hunt "B" Well No. 1

Location App Center Sec. 14 Twp. 33 Rge. 33 (E) (W)

County Seward Total Depth 2745'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 10:00 AM Day 21 Month 3 Year 1972

The above well was plugged as follows:

8 5/8" to 880' circulated w/ cement. 5 1/2" to 2745' cement circulated.

Top perforations 2574' Plug bottom w/ 20 sacks cement.

Top of cement 2534' Mud 2534' to 958'

Spotted 15 sacks cement 958' to 853' Mud 853' to 50'

Plug. Hulls & 5 sacks cement 50' to 0' Company Pump

No pipe pulled.

I hereby certify that the above well was plugged as herein stated.

Signed:   
Well Plugging Supervisor

INVOICED

DATE 3-23-72

INV. NO. 5383-10