

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION GNSW $\frac{1}{4}$ of SW $\frac{1}{4}$

SEC. 12 TWP. 33 RGE. 30

Dry Hole * Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. A1 Lease Bruno Meyer

Operator Columbian Fuel Corp. Address Ulysses, Kansas.

Field _____ County Seward

Total Depth 6500 Feet.

(Describe briefly the manner in which the well was plugged)

Drilled to 6500 ft. Plugged back to 3688' with 10 lb. mud 51 viscosity through
drill pipe. 5 $\frac{1}{2}$ casing set at 3676 and cemented with 75 sacks of cement.
Perf. at 3607 to 3609 and squeezed with 200 sacks of cement. Fifteen feet of
cement from bottom of 9 5/8 casing, 2879 to 2894, pumped in casing.
Plugged with heavy mud from 2879 to 15 feet of top. 15 feet of cement left in
top of hole. Both 13 3/8 and 9 5/8 casing cement was circulated.

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1950

CONSERVATION DIVISION
Wichita, Kansas

R. J. Phillips
District Conservation Agent

Date October 9-1950

PLUGGING
FILE SEC. 12 TWP. 33 RGE. 30
BOOK PAGE 32 LINE 27