

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Panhandle Development Co., Inc.

Complete Address: P. O. Box 1226, Liberal, Kansas

Lease Name Stoddard Well No. 1

Location C SW ~~SW~~ SE Sec. 11 Twp. 33S Rge. 31W (E) (W)

County Seward Total Depth 6053'

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ray's Tubing & Casing Service

Address: Liberal, Kansas License No.

Operation Completed: Hour Day 12 Month April Year 1961

The Above well was plugged as follows:

Dumped 175 gallons gravel, hole bridged at 3318', dumped 5 sacks cement, top of plug
at 3290', ran free point and cut casing at 2816'. Pulled one joint 5 1/2" casing.
Hydraulic pump broke down. Down for repairs 4-21,22,23,24,and 25. Start pulling casing
4-26-61. Pulled 87 joints and piece 2828.92' overall. 4-30-61, ran free point on 8 5/8"
casing to 550'. Cut off casing. Recovered 549.50' of 8 5/8" 24 # casing. Put rock
bridge back to 510'. Dumped 30 sacks cement. Filled with mud to 40', placed rock
bridge and dumped 15 sacks cement. Cut off Braden head and welded steel plate on top
of 13 3/8" casing. Plugging completed 1:00 P.M. 5-2-61.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/26/62
INV. NO. 5419-W

Signed: W. F. Laekamp
Well Plugging Supervisor
by S. S. Greener