

15-175-10118-000/P

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cleary Petroleum Inc.

Complete Address: 310 Kermac Building, Oklahoma City, Oklahoma

Lease Name Sheldon Well No. 1

Location SW SW Sec. 14 Twp. 33 Rge. 31 ~~(E)~~ (W)

County Seward Total Depth ~~500'~~ 6063'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Gayle E. Toland

Address: Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:30 PM Day 22 Month 5 Year 1968

The Above well was plugged as follows:

8 5/8" to 150' circulated w/ cement. 5 1/2" to 6063' cemented.

Top perforations 4910' Plug bottom w/ 25 sacks cement.

Top of cement 4878' Mud 4878' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 180'

Spotted 30 sacks cement 180' to 80' Mud 80' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 2200' of 5 1/8" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Eves
Well Plugging Supervisor

INVOICED
DATE 5-24-68
INV. NO. 7803-11