

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

Authority May 26, 1980
API Number 15 - - (of this well)

Operator's Full Name William Gruenerwaldt Associates Inc.
Complete Address Antlers Plaza, Box 909, Colo Springs, Colo.
Lease Name Burr Well No. 1
Location C. W. W. W. Sec. 4 Twp. 33 Rge. 31 (E) (W) 2
County Seward Total Depth 6050
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Sargent's Casing Pulling, Inc
Address Liberal Kansas License No. 511

Operation Completed: Hour 3:00 PM Day 20 Month May Year 1980

The above well was plugged as follows:

There was 1560' of 8 1/2" surface casing
4 1/2" casing set 6050'. Perforations were
5069-5050. 1st plug at 5069-4800' with
20 lbs cement 1 hull. 2nd plug at 1500'
1400' with 35 lbs cement. 3rd plug at
750-625' with 25 lbs cement. 4th plug
at 40-0 with 10 lbs cement.
There was 2610' of 4 1/2" casing salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-22-80
INV. NO. 2216-w

Signed: Thomas
Well Plugging Supervisor
STATE CORPORATION COMMISSION

MAY 22 1980

CONSERVATION DIVISION
Wichita, Kansas